




REPUBLIC OF THE PHILIPPINES  
**NATIONAL DISASTER RISK REDUCTION AND MANAGEMENT COUNCIL**

National Disaster Risk Reduction and Management Center, Camp Aguinaldo, Quezon City, Philippines

## NDRRMC UPDATE

### Taal, Mayon, and Kanlaon Volcano Bulletin

Releasing Officer:

  
**UNDERSECRETARY RICARDO B JALAD**  
Executive Director, NDRRMC and  
Administrator, OCD

**DATE : 20 May 2020, 8:00 AM**

Source: DOST-PHIVOLCS

#### I. SITUATION OVERVIEW

##### A. ALERT STATUS OF TAAL VOLCANO

In the past 24-hour period, the Taal Volcano Network **recorded eleven (11) volcanic earthquakes** that are associated mainly with rock-fracturing processes beneath and around the edifice. Weak steaming or fumarolic activity rising 100 to 300 meters high before drifting southwest was observed from vents on the Main Crater and fissure vents along the Daang Kastila Trail.

**Alert Level 1 (Abnormal)** is maintained over Taal Volcano. DOST-PHIVOLCS reminds the public that at Alert Level 1, sudden steam-driven or phreatic explosions, volcanic earthquakes, minor ashfall and lethal accumulations or expulsions of volcanic gas can occur and threaten areas within the Taal Volcano Island (TVI). DOSTPHIVOLCS strongly recommends that entry into TVI, Taal's Permanent Danger Zone or PDZ, especially the vicinities of the Main Crater and the Daang Kastila fissure, must remain strictly prohibited. Local government units are advised to continuously assess previously evacuated barangays around Taal Lake for damages and road accessibilities and to strengthen preparedness, contingency and communication measures in case of renewed unrest. People are also advised to observe precautions due to ground displacement across fissures, possible ashfall and minor earthquakes. Civil aviation authorities must advise pilots to avoid flying close to the volcano as airborne ash and ballistic fragments from sudden explosions and wind-remobilized ash may pose hazards to aircraft.

##### B. ALERT STATUS OF MAYON VOLCANO

Mayon Volcano's seismic monitoring network did not detect any volcanic earthquake during the 24-hour observation period. Moderate emission of white steam-laden that drifted north-northwest and north-northeast was observed. Faint crater glow from the summit could be observed at night. Sulfur dioxide (SO<sub>2</sub>) emission was measured at an average of 338 tonnes/day on 8 May 2020. Recent electronic tilt data showed inflation of the middle to upper portions of the volcanic edifice that began in the last quarter of 2019.



This follows an inflationary trend that began in February 2019 as recorded by continuous GPS monitoring.

**DOST-PHIVOLCS reiterates that Alert Level 2 currently prevails over Mayon because the volcano is at a moderate level of unrest.** It is therefore strongly recommended that entry into the six kilometer-radius Permanent Danger Zone or PDZ and a precautionary seven kilometer-radius Extended Danger Zone or EDZ in the south-southwest to east-northeast sector, stretching from Anoling, Camalig to Sta. Misericordia, Sto. Domingo should be strictly prohibited. The public is reminded that sudden explosions, lava collapse, pyroclastic density currents or PDCs and ashfall can occur without warning and threaten areas in the upper to middle slopes of Mayon. People residing close to these danger areas are also advised to observe precautions against rockfalls, PDCs, and ashfall. Active stream/river channels and those identified as perennially lahar-prone areas on all sectors of the volcano should also be avoided especially during extreme weather conditions when there is heavy and prolonged rainfall. Civil aviation authorities must advise pilots to avoid flying close to the volcano's summit as airborne ash and ballistic fragments from sudden explosions and PDCs may pose hazards to aircraft.

### C. ALERT STATUS OF KANLAON VOLCANO

Kanlaon Volcano's seismic monitoring network **recorded six (6) volcanic earthquakes** during the 24-hour observation period. Moderate emission of white steam-laden plumes rising 300 meters high before drifting northwest to southwest was observed. Ground deformation data from continuous GPS measurements indicate a slight deflation of the lower and mid slopes since January 2020. Short-term electronic tilt monitoring on the southeastern flanks recorded pronounced inflation of the upper slopes at the end of January 2020. These parameters indicate that hydrothermal or magmatic activity is occurring deep beneath the edifice.

**Alert Level 1 (abnormal)** status prevails over Kanlaon Volcano, which means that it is at an abnormal condition and has entered a period of unrest. The local government units and the public are strongly reminded that entry into the 4-kilometer radius Permanent Danger Zone (PDZ) must be strictly prohibited due to the further possibilities of sudden and hazardous steam-driven or phreatic eruptions. Civil aviation authorities must also advise pilots to avoid flying close to the volcano's summit as ejecta from any sudden phreatic eruption can be hazardous to aircraft. DOST-PHIVOLCS is closely monitoring Kanlaon Volcano's activity and any new development will be relayed to all concerned.

DOST-PHIVOLCS is closely monitoring all of the abovementioned Volcanos' activities and any new development will be relayed to all concerned.

### II. ACTIONS TAKEN

1. NDRRM Operations Center prepared NDRRMC Advisory and Update, and disseminated the same to **OCD Regional Centers CALABARZON, V, and VI** through NDRRMC website in order to closely monitor the situation and take appropriate actions for any new development.
  2. Concerned NDRRMC member-agencies were provided with a copy of the Memorandum for the SND.
  3. DOST-PHIVOLCS is closely monitoring the activities of Taal, Mayon, and Kanlaon Volcanoes and any new development will be relayed to all concerned.
-